G. R. S. 59] GPB—15,000 20 12 13

GENERAL AND REVENUE SECRETARIAT.

1898-99
191 .
( Miscellaneous )

# File No. 107

## Serial Nos.

## Papers Filed.

*Month*_____

SUBJECT.

Sanctioning an Estimate for Rs 1376 for repairing the Chamarajendra Sanskrit College, Bangalore -

| PREVIOUS REFERENCES. | LATER REFERENCES. |
| --- | --- |
| | |

Order

699

Mur. F. 32-95

dt 12/12/98

Sanction is accorded to the accompanying Estimate for Rs 1376 prepared under the orders of the Mysore Superintendent to repair the Sri Chamarajendra Sanskrit College in Bangalore Fort. The charge will be met from the State Grant of Rs 15000 sanctioned for the repairs of Mysore Institutions during 1898-2. and the amount will be paid on presentation of a Bill countersigned by the Mys: Superintendent

To
The Comptr
with a copy of the
Abstt: Estimate

AS
Mys: Secy

Estimate of the probable cost of executing certain repairs to Chamarajendra Sanscrit College Fort Bangalore.

| Details | No | Dimensions | | | Contents | Total |
|---|---|---|---|---|---|---|
| excavating soil one foot deep, clearing and forming road surface. | | | | | | |
| Main Road work to south. | 1 | 164 | 13 | 0 | 2132 | |
| East side ditto | 1 | 60 | 19 | 0 | 1140 | |
| Foot path to Library | 1 | 70 | 5 | 0 | 350 | |
| Circular plot in front | 1 | 80 | 8 | 0 | 640 | |
| Foot path to east | 1 | 47 | 5 | 0 | 235 | |
| Ditto to west | 1 | 50 | 5 | 0 | 250 | |
| Total square feet | | | | | 4747 | |
| | | | | are | Yards | 527 |
| Coating with 3" of gravel including collection, rolling, watering &c Comp | | 527 | 0 | 1/2 | 44 | 44 |
| Sanding including collection | | 527 | 0 | 1/72 | 7 | 7 |
| Cut stone gate posts including | 4 | 9 | 1/3 | 1/3 | 4 | 4 |
| Drilling holes with iron work &c Com | 2 | | | | 2 | 2 |
| Sundry repairs to plastering here & there | | No. | of | yrs | 1000 | 1000 |
| Repairing doors and windows | 1 | Item | | | 1 | 1 |
| Fixing bound stones | 1 | Item | | | 1 | 1 |
| Laying V. shape drain (2'x2') | 1 | 120 | Rft | | 120 | 120 |
| Ditto (1'x1') | 1 | 60 | Rft | | 60 | 60 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| N. W | Earth work. | | | | | | |
| | Stoning with Broken Stone | 1 | 15 | 1½ | 6 | 135.0 | |
| | Stone Slabs for flooring | 2 | 3½ | 2' | " | 14 | |
| | Ditto | 2' | 8 | 2 | 0 | 32 | |
| | Total cost | | | | | | 46. |
| | Brick Masonry in Bricklime cement | | | | | | |
| | Foundation & Masonry Reservoir | 1 | 0. | 5 | 2.2 | 20000 | 20000 |
| | Coloumns & Arches & Arch Bricks Masonry & Cupola work | 1 | 0. | 5 | 2.2 | 120.00 | 120.00 |
| | Flooring with brick on edge and plaster with Mortar 2 coats Cinder & R.C. | 1 | 96 | 18¼ | 0 | 1752 | 1752 |
| | Flooring with Round brick in mud & plastering with Mortar 2 coats. | | | | | | |
| | Room | 1 | 27¾ | 18¼ | 0 | 506 | |
| | Ditto | 1 | 21½ | 18 | 0 | 387 | |
| | Ditto | 1 | 14¼ | 18 | 0 | 256 | |
| | Ditto Library | 1 | 23½ | 18 | 0 | 423 | |
| | Ditto | 1 | 14½ | 10 | 0 | 145 | |
| | Ditto | 1 | 43¾ | 18¼ | 0 | 451 | |
| | Ditto | 1 | 18 | 18¼ | 0 | 328 | |
| | Ditto | 1 | 16¾ | 18 | 0 | | |
| | Ditto | 1 | 14 | 18 | 0 | 252 | |
| | Ditto | 1 | 23½ | 18 | 0 | 423 | |
| | Ditto | 1 | 24 | 10 | 0 | 240 | |
| | Total Square | | | | | | 37.84 |
| | Bar at Brick in Cement. | | | | | | |
| | Right wing Corner wall. | 1 | 70 | 24 | 1 | 187 | |
| | Ditto | 1 | 9 | 24 | 1 | 24 | |
| | Ditto | | | | | | |
| | Left wing Ditto | 5 | 4 | ½ | 1 | 10 | |
| | Ditto | 1 | 80 | 2 | 1 | 100 | |
| | Arch of Library | 1 | 29 | 1½ | 1¼ | 110 | 52 |
| | Ditto | 1 | 57 | 1½ | 1 | 88 | ½ |
| | Parapet wall round roof | 2 | 5½ | 1 | 3 | 33 | |
| | Arch | 2 | 2 | 1 | 2 | | |
| | Total cubic feet | | | | | | 63 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| wt plastering | Right wing | 1 | 84 | 3 | " | 252 | |
| Ditto | Left wing | 1 | 80 | 2½ | " | 200 | |
| Around Library room. | | 1 | 118 | 2 | " | 236. | |
| | Total Sqr ares | | | | | | 6.88. |
| Dismantling roof and shifting tiles by using ¼ new pantiles & 4 tiles here & there with Chunam | | | | | | | |
| Plastering &c Complete —— | | 2 | 170 | 13½ | " | 45.90 | |
| Ditto | | 4 | 75 | 13½ | " | 40 50 | |
| | Total Squares | | | | | | 8640. |
| Earthwork. Carting earth & filling in cuts here and there the Compound and levelling and | | | | | | | |
| Clearing Rubbish &c | | Lo | | Cyft | | 2.50 | 250. |
| Chocolate Painting | | | | | | | |
| Doors | | 10 | 7¾ | 4½ | " | 348 | |
| Ditto | | 20 | 3½ | 6¼ | " | 438 | |
| Windows | 2×36= | 72 | 5½ | 4 | " | 15 84 | |
| L. room doors | | 2 | 6 | 2¾ | " | 33 | |
| Windows | | 4 | 3 | 3½ | " | 42 | |
| Magazine building | | | Lo | Sqrs | | 2.00 | |
| | Total Sqrs. | | | | | | 26.45. |

Bangalore
1/10/98

B. Ramaiah
Junior Draftsman

# Abstract

| Particulars | Quantity | Rate | Amount Total |
|---|---|---|---|
| Picking road surface as per details | 527 Sqs | @ 6 | 16. |
| Gravelling including collection | 44 Cft | @ 13 | 36. |
| Sanding do | 7 " | @ 8 " | 4 |
| Cut stone gate posts | 4 E | ~~25~~ 5 @ " | ~~80~~ |
| Drilling holes &c | 2 E | 6 @ " | 12 |
| Plastering with Chunam | 1000 Sqs | 2 8 " | 25 |
| Repairing doors & windows | 1 Lo. | 10 @ " | 10 |
| Fixing boundstones for grade | 1 Lo | 5 @ " | 5 |
| Laying V. drain 2"x2" with cement joints | 120 Rft | @ 8 " | 60 |
| Ditto 1"x1" Do | 60 " | @ 4 " | 15 |
| Earthwork for well | 35 Cft | @ 2 6 | 5 |
| Well steining with Burnt stone | 450 Cft | @ 1 6 | 42 |
| Stone Slabbing | 46 Sft | @ 2 " | 6 |
| Whitewashing | 2000 Sqs | @ ~~2 8~~ | 25 |
| Colour washing | 1200 " | @ 4 " | 30 |
| Flooring with Brick Concrete & plastering 2 coats | 17 52 Sqs | 4 8 @ | ~~79~~ |
| Ditto with Burnt Bricks &c &c | 37.84 " | ~~5~~ 4 @ " | ~~189~~ 151 |
| Burnt Brick in Chunam | 631 Cft | @ 2 6 | 99 |
| Cement plastering | 6.88 Sqs | ~~8~~ 7 @ " | ~~55~~ 48 |
| Shifting tiles by using ¼ new pan tiles for tiles here & there & chunam plastering | 86.40 " | ~~5~~ 4 8 @ " | 387 ~~432~~ |
| Earth work. Casting for compound & levelling earth | 250 " | @ 5 " | 78 |
| Chocolate painting | 26.45 Sqs | @ 4 " | 60 |
| Total Rupees | | | ~~1401~~ 1311 |
| Contingencies at 5 per % | | | ~~69~~ 65 |
| Grand total Rupees | | | ~~1470~~ 1376 |

Bangalore
1/10/98

Checked
BK.

B. Hanumaiah
Executive Engineer

MUZRAI

1898

*From*

The Secy: to the Govt of

*To* Mysore

The Comptroller

*Dated* 20 December

*Despatched* 29

*Received*

*General No.* 753

*Muzrai F. No.* 32-95

*Enclosure No.* 1

Govt Pro no: 699

Muz 32-95

dated 12th December 1898

sanctioning an Estimate

for Rs 1376 for the repairs

of the Chamarajendra

Sanskrit College in

Bangalore Fort.

Has the honour to

forward herewith a bill

duly countersigned

for Rs 800 on

account of ~~repairs~~

work executed towards the repairs of the College sanctioned in the above and to request that the bill may be audited and returned to this office for payment.

By order

Al

Mus Treg:

Measurement of work done on executing certain
Repairs to Chamarajendra Sanscrit College Fort
Bangalore

| Details | No | Dimensions | Contents | Per | Rate | Amount | Total |
|---|---|---|---|---|---|---|---|
| Excavating soil one foot deep clearing grass roots and forming road | | | | | | | |
| Main road N & South | 1 | 164 13 | 1132 | | | | |
| East side — do — | 1 | 60 19 | 1140 | | | | |
| Foot path to library | 1 | 70 5 | 350 | | | | |
| Circular plot in front | 1 | 80 8 | 640 | | | | |
| Foot path to east | 1 | 47 5 | 235 | | | | |
| Ditto to west | 1 | 50 5 | 250 | | | | |
| Total square feet 4747 | | | | | | | |
| | | | Square yards | 527 | Sqds | @ 6 | 16 / 6 |
| Coating with 3 of gravel including collection, rolling, watering & complete | 1 | 527 1/2 | 44 | 44 | Cpds | @ 13 | 35 1/2 |
| Sanding including collection | 1 | 527 1/2 | 1 | 1 | " | @ 8 | 3 8 |
| Well Earthwork Excavation | 1 | 15 dia 9 | 954 | | | | |
| Stone Steining for do | | Cft do | | 35 | | @ 26 | 5 / 6 |
| Stone Slabs for floor | 1 | 15 1 1/2 | 450 | 450 | | @ 1 6 | 42 3 |
| — do — | 2 | 3 1/2 2 | 14 | | | | |
| — do — | 2 | 8 2 | 32 | | | | |
| Total square feet | | | | 46 | Sft | @ 2 | 5 12 |
| Flooring with brick Concrete & plastering with mortar 2 coats — | | | | | | | |
| Central Hall | 1 | 96 18 1/4 | 175 | 17.5 | S. | 4 8 | 78 13 |
| Flooring with Burnt Brick in mud & plastering 2 Coats including excavating and removing soil — | | | | | | | |
| Rooms | 1 | 27 3/4 18 1/4 | 50 | | | | |
| — Ditto | 1 | 21 1/2 18 | 3 | | | | |
| — Ditto | 1 | 14 1/2 18 | 25 | | | | |
| — Ditto | 1 | 23 1/2 18 | 423 | | | | |
| — Ditto — Library room | 1 | 14 1/2 10 | 14 | | | | |
| — Ditto | 1 | 24 3/4 18 1/4 | 451 | | | | |
| — Ditto | 1 | 18 18 1/4 | 32 | | | | |
| — Ditto | 1 | 20 3/4 18 | 37 | | | | |
| — Ditto | 1 | 14 1/2 18 | 25 | | | | |

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | 187 | 15 | |
| | | | | | | | | | | 98 | | |
| Brick flooring & plastering | | | | | | | | | | | | |
| 2 coats. Room as Continued | 1 | 23½ | 18 | | 423 | | | | | | | |
| — Ditto — | 1 | 24 | 10 | | 240 | | | | | | | |
| Total squares | | | | | | 37.84 | Sqs | 5 | 189 | 8 | - | |
| | | | | | | | | 6 | 22 | 1 | 4 | |
| Burnt Brick in Chunam. | | | | | | | | | | | | |
| Right wing by the side of rear wall. — | 1 | 75 | 2½ | 1 | 187 | | | | | | | |
| Ditto — | 1 | 9 | 2½ | 1 | 24 | | | | | | | |
| Ditto — | 5 | 4 | ½ | 1 | 10 | | | | | | | |
| Left wing do — | 1 | 80 | 2 | 1 | 160 | | | | | | | |
| Around library — | 1 | 59 | 1½ | 1¼ | 110½ | | | | | | | |
| Ditto — | 1 | 59 | ½ | ¾ | 66 | | | | | | | |
| Parrapet around well | 2 | 5½ | 1 | 3 | 33 | | | | | | | |
| Ditto — | 2 | 3 | 1 | 3 | 18 | | | | | | | |
| Total c/f | | | | | | 608½ | Cft | @ | 2 | 6 | 9 | 5 1 3 |
| Cement plastering | | | | | | | | | | | | |
| for - do - Right wing | 1 | 84 | 3 | @ | 252 | | | | | | | |
| do - Left wing — | 1 | 80 | 2½ | @ | 200 | | | | | | | |
| Around library room | 1 | 118 | 2 | @ | 236 | | | | | | | |
| Total squares | | | | | | 6.88 | Sqs | 8 | @ | 55 | @ | Disallowed at present |
| Dismantling and | | | | | | | | | | | | |
| Reroofing & shifting | | | | | | | | | | | | |
| tiles by moving ¼ new | | | | | | | | | | | | |
| pan tiles and flat | | | | | | | | | | | | |
| tiles here & there with chu- | | | | | | | | | | | | |
| -nam plastering &c Cft | 2 | 170 | 1½ | @ | 45.90 | | | | | | | |
| — Ditto — | 4 | 75 | 1½ | @ | 405.0 | | | | | | | |
| Total squares | | | | | | 86.40 | Sqs | 4 | 8 | - | 388 | 12 0 |
| | | | | | | | | 5 | @ | 432 | @ | |
| Sundry repairs to | | | | | | | | | | | | |
| plaster & there &c | | | | | | Sqs | 6.00 | 6.00 | @ | 8 | @ | 15 @ |
| Total Rupees | | | | | | | | | | | | 876 0 3 |
| | | | | | | | | | | | | 1676 1 3 |
| Deduct for bad work | | | | | | | | | | | | 776 0 3 |
| Net amount to be paid at present | | | | | | | | | | | | 800 0 0 |

Bangalore
1/10/98

Checked

B. Hanumiah
Mistri Overseer

In obedience to your orders I inspected and checked the measurements for the repairs of the Chamarajendra Sanskrit college Bangalore, and beg to submit the following report:-

The main items of the repairs as per measurement list are:-

(1) Shifting and relaying the tiles of the roof. A sum of Rs 432 has been charged for this work at Rs 5 per sqr: As the shifting &c was done only 3 years back at ~~a cost~~ the rate of Rs 4½4 by the contractors Lankappa & Hanumiah I dont think that many tiles (new) have been used so the rate ~~of 5~~ may be reduced from Rs 5 to Rs 4/8

(2) Flooring all rooms except the Hall This is done with one course of Brick in Chunam with a coat of chunam

plastering. The floor contains many small ruts and I am sure the flooring will not last even for a couple of years. I think Rs 4/8 or 5 a sqr is reasonable instead of 6.

(3) The making of the road. This ~~not~~ has not been done properly as the grass is overgrowing though it was done only 3 months back and after my remark about the thing to the ~~contractor~~ he has quietly cut the bits of the grass which process simply encourages the growth.

(4) The cement plastering that is done to the side of the walls is no cement plastering but simply plastered with chunam and washed with cement and therefore this item may be disallowed altogether at present.

As for the measurements and other work they are fair and very satisfactory

Draft. BK

Measurement

Abstract of ~~Estimate~~ for th repairs to ~~the~~ ~~Sri~~ Chamarajendra Sanskrit college

in Bangalore Taluk District

| Particulars | Per | Rate Rs. | a. | p | Quantity | Cost Rs | a. | p. |
|---|---|---|---|---|---|---|---|---|
| Picking road surface ~~as per details~~ | Syd. | - | - | 6 | 527 | 16 | 7 | 6 |
| Travelling including collection. | c.yd. | - | 13 | - | 44 | 35 | 12 | - |
| Sanding - do - | " | - | 8 | | 7 | 3 | 8 | - |
| Earth work for well. | c.yd. | | 2 | 6 | 35 | 5 | 7 | 6 |
| Stone Construction for - do - | c.ft. | | 1 | 6 | 480 | 42 | 3 | - |
| Stone slabs for floor of do - | S.ft. | - | 2 | - | 46 | 5 | 12 | - |
| Flooring the hall with brick concrete and plastering | Sqr | 4 | 8 | - | 17.52 | 78 | 13 | - |
| Flooring the rooms with Burnt brick in mud | Sqr | 5 | - | - | 37.84 | 189 | 3 | 2 |
| Burnt brick in chunnam for walls of the main building | c.ft. | | 2 | 6 | 608½ | 95 | 1 | 3 |
| Dismantling and reroofing and including Shifting tiles by using ¼ new pan tiles and flat tiles ~~here and there~~ to with chunnam plastering &c Complete | Sqr | 4 | 8 | - | 86.40 | 388 | 12 | 10 |
| Sundry repairs such as plastering ~~here & there~~ to walls of main building | Sqr | 2 | 8 | - | 6.00 | 15 | - | - |
| Total Rupees | | | | | | 876 | 0 | 3 |
| Deduct for bad work. | | | | | | 76 | 0 | 3 |
| Balance Rupees | | | | | | | | |
| Net amount to be paid ~~at~~ | | | | | | 800 | 0 | 0 |

Bangalore
9th December 1895

Krishna a
r

Draft.

Sanctioned in Govt. Proceedings No. _____ dated

[Form A.]

The ..... Government ..... of ..... Mysore ..... Dr

| Particulars. | Amount. | Remarks. |
|---|---|---|
| On account of the repairs executed to the Chamarajendra Sanskrit College in Bangalore Fort. as per Abstract measurement list, copy of which is appended. | 800 | Work sanctioned in Govt Pro no. 699 MW2732-95 dated 12th December |

To be made payable in the State Huzur Treasury.

Murrai Superintendent
Asst.

[illegible]

ಕೊಟ್ಟಿರುವ ಸಂಖ್ಯೆಗಳಿಗೆ ಸಮಾನವಾದ ಸಂಖ್ಯೆಗಳನ್ನು ಬರೆಯಿರಿ.

೧೦ ಮಿಂ ೫೦ ಮಿಂ ೨೪ ಗಂ ೨೪ ಗಂ ೧೫ ದಿನ ೧೫ ದಿನ

ಸಮಾನವಾದ ಸಂಖ್ಯೆಗಳನ್ನು ಬರೆಯಿರಿ.

೧೦ ಮಿಂ ೫೦ ಮಿಂ ೨೪ ಗಂ ೨೪ ಗಂ ೧೫ ದಿನ ೧೫ ದಿನ

೨೦೦೪ ನೇ ಇಸವಿಯ ಜನವರಿ ತಿಂಗಳಿನಲ್ಲಿ ಎಷ್ಟು ದಿನಗಳಿವೆ?

ಸಮಾನವಾದ ಸಂಖ್ಯೆಗಳನ್ನು ಬರೆಯಿರಿ.

೧೦ ಮಿಂ ೫೦ ಮಿಂ ೨೪ ಗಂ ೨೪ ಗಂ ೧೫ ದಿನ ೧೫ ದಿನ

೨೦೦೪ ನೇ ಇಸವಿಯ ಜನವರಿ ತಿಂಗಳಿನಲ್ಲಿ ಎಷ್ಟು ದಿನಗಳಿವೆ?

ಸಮಾನವಾದ ಸಂಖ್ಯೆಗಳನ್ನು ಬರೆಯಿರಿ.

೧೦ ಮಿಂ ೫೦ ಮಿಂ ೨೪ ಗಂ ೨೪ ಗಂ ೧೫ ದಿನ ೧೫ ದಿನ

೨೦೦೪ ನೇ ಇಸವಿಯ ಜನವರಿ ತಿಂಗಳಿನಲ್ಲಿ ಎಷ್ಟು ದಿನಗಳಿವೆ?

ಸಮಾನವಾದ ಸಂಖ್ಯೆಗಳನ್ನು ಬರೆಯಿರಿ.

೧೦ ಮಿಂ ೫೦ ಮಿಂ ೨೪ ಗಂ ೨೪ ಗಂ ೧೫ ದಿನ ೧೫ ದಿನ

೨೦೦೪ ನೇ ಇಸವಿಯ ಜನವರಿ ತಿಂಗಳಿನಲ್ಲಿ ಎಷ್ಟು ದಿನಗಳಿವೆ?

ಕಾಲಮಾನ ಮತ್ತು ಸಂಖ್ಯೆಗಳ ಬಳಕೆ

ಕಾಲಮಾನ ಮತ್ತು ಸಂಖ್ಯೆಗಳ ಬಳಕೆ :

2-1-99

Sd/-

R. Jaya Rao Dt. Hd. Record Keepers

Head Munshi

Anugrai Dept's office

Abstract of ~~Estimate for~~ Measurement for the repairs to the Chamarajendra Sanskrit College in Bangalore Fort

| Particulars, | Per. | Rate. Rs. | Rate. A. | Rate. P | Quantity. | Cost. Rs. | Cost. A. | Cost. P |
|---|---|---|---|---|---|---|---|---|
| Picking road surface. | Syd. | - | | 6 | 527 | 16 | 7 | 6 |
| Gravelling including collection | cyd. | - | 13 | - | 44 | 35 | 12 | |
| Sanding — do — | " | - | 8 | - | 7 | 3 | 8 | |
| Earthwork for well. | cyd. | - | 2 | 6 | 35 | 5 | 7 | 6 |
| Stone construction for do. | Cft. | - | 1 | 6 | 450 | 42 | 3 | - |
| Stone slabs for floor of do. | Sft. | - | 2 | - | 46 | 5 | 12 | |
| Flooring the hall with brick Concrete and plastering | Sqr | 4 | 8 | - | 17.52 | 78 | 13 | - |
| Flooring the rooms with burnt brick in mud and plastering | Sqr | 5 | - | - | 37.84 | 189 | 3 | 2 |
| Burnt brick in chunnam. | Cft. | - | 2 | 6 | 608½ | 95 | 1 | 3 |
| Dismantling and reroofing — including shifting tiles by using ¼ new pan tiles and flat tiles &c with chunnam plastering &c complete. | Sqr | 4 | 8 | - | 86.40 | 388 | 12 | 10 |
| Sundry repairs such as plastering to walls of main buildings | Sqr | 2 | 8 | - | 6.00 | 15 | - | - |
| | | | | | Total | 876 | 0 | 3 |
| | | | | | Deduct for work | 76 | 0 | 3 |
| | | | | | Balance | 800 | - | |

Bangalore 9th December 1873

(Sd) Ranganna

Sanctioned for Rs.

No. dated

"Copy"

A true Copy

Murad Secretary

Murad overseer in Govt. Pros.

This is the draft
to submitted for
approval If approved,
I shall fairecopy it
and get the Contractor's
signature with one
anna stamp duly
affixed.

I have also written
the necessary endorsement
on the Audited Bill

29/12/98